

June 21, 2023



PROJECT: City of Coburg Operations Building and Operations Storage Building Project

ADDENDUM #2

Branch Engineering Inc. Project No. 20-004j

The following clarifications and revisions for the above-referenced project are hereby incorporated by Addendum to the previously issued bid documents:

Project Manual – Section 020 – Scope of Work -The attached Addendum #2 Scope of Work supersedes the previously issued Scope of Work in its entirety.

Project Manual – Section 020 – City Schedule - *Revision:* The Bid Closed/Opened & Read Date will be extended to 2:00pm on July 20, 2023.

Project Manual – Section 020 – City Schedule - *Revision:* The Projected Award Date for this project has been changed to August 8, 2023.

Project Manual - Section 020 - City Schedule - *Revision:* The Projected Start Date for this project has been changed to August 21, 2023.

Project Manual – Section 020 – City Schedule - *Revision:* The Project Substantial Completion Date for this project has been changed to June 28, 2024.

Project Manual – Section 020 – City Schedule - *Revision:* The Project Final Completion Date for this project has been changed to July 26, 2024.

Project Manual - Section 700 - *Revision: Delete* all references to "Division 01" and *Replace* with "Section 400"

General Clarification - Space Conditioning Requirements -

Building #1: Main Building (Rooms #101 and 107) shall be Semi-Heated space with a heating system provided by shop heaters located per sheet A103. Rooms #102-106 and connected spaces shall be fully conditioned space with heating/cooling provided by SPLIT-SYSTEM VRV AIR CONDITIONER(S). **Building** #2: Building shall be unheated space.

Project Manual - Section 700 - Division 08 - Section 083613 2.1.D.2.b.1) - *Revision: Delete* this entry in its entirety and *Replace* with the following:

1) Steel Sheet Thickness: 24gauge minimum nominal coated thickness.

Project Manual - Section 700 - Division 26 - Section 260000 2.4.B - *Revision: Delete* this entry in its entirety and *Replace with the following:*

B. Provide means of egress artificial lighting with emergency power as indicated in Drawings.

Project Manual - Section 700 - Addition: The attached Geotechnical Report

Geotechnical Report - The attached Geotechnical Report is included as part of Addendum #2.

CONTRACTOR QUESTIONS:

• *Contractor Question* – Building #1 – C102: Any spec on septic requirement? Who supplies and installs the transformer vault?

- Response Per note 302 on sheet C102, the Septic tank is furnished and installed by Owner. Per note 500 on C102, the electrical transformer is furnished and installed by Owner.
- Contractor Question Building #1 C105: What are the power requirements for the smaller building?
 - o **Response** Electrical design/build is delegated to the Contractor. Per CRFD Storage Building Sheet A103 Sheet Note #1 "...Schematic specialty electrical receptacles [shown here]...All other electrical work shall be per the current adopted version of the applicable electrical code." Per Section 700 Division 260000 Electrical Provisions "All work covered under these provisions is to be 'design/build' by contractor utilizing specific equipment and materials as may be specified elsewhere in project Drawings or Specifications."
- *Contractor Question* Building #1 A101: Under legend, the panels are indicated to be 400-amp 277/480 volt. Is this correct? Are they to be 120/208 volt instead?
 - *Response* Per A101 LEGEND, 3-Phase CT Cabinet, Test Switch, 9S Meter Base (400A) 480/277V Service per <u>EPUD</u> Electrical Standards. No electrical panels have been specified here. Electrical design/build is delegated to the Contractor.
 - Clarification Remove "EWEB" from this note in the Drawings sheet A101 and Replace with "EPUD".
- **Contractor Question** Building #1 A101: What is required for the emergency backup system? Wattage? Amperage?
 - Response Per Section 700 Division 260000 2.4C Emergency Power Backup Electrical System Basis of Design: Basis of design shall include all products and accessories to assemble and install a complete 8kW Power with 28.8kWh effective energy storage SystemEdge Radian emergency power system as manufactured by Outback Power Alpha Technologies Services, Inc.
- *Contractor Question* Building #1 A101: There are 10 outlets with an emergency designation. Do they need a dedicated circuit?
 - o *Response* Electrical design/build is delegated to the Contractor. Electrical work shall be per the current adopted version of the applicable code.
- *Contractor Question* Building #1 A101: What is required at the 30-, 50-, and 60-amp outlets on the plan? Single phase or three phase? Voltage? I am assuming that the power for the small building is fed from panels in the larger building. Confirm?
 - o **Response** The Owner does not intend to install any 3-phase equipment in Building #1. See Note #505 on Sheet C105 for information regarding electrical service for the Building #2 (CRFD Storage Building).
- Contractor Question Building #1 A102: Is there a need for any power outlets?
 - Response Electrical design/build is delegated to the Contractor. Electrical work shall be per the current adopted version of the applicable electrical code. Coordinate with Owner during Construction.
- *Contractor Question* Building #1 A103: Is there a need for emergency lighting in the office area?
 - o **Response** Emergency power for illumination requirements are per A103 Means of Egress Illumination Notes #3 & #4. The floor areas required to be illuminated by Emergency Egress Lighting are also shown on Sheet G001 Egress Plan.
 - *Clarification* -Emergency Egress Lighting hatching has been inadvertently omitted at the exit door opening onto the Open Bay area. This lighting is specified correctly on Sheet A103, therefore no revision to the Drawings will be issued at this time.

Branch Engineering, Inc. 2 of 3

- *Contractor Question* Building #1 A103: What is required for switching of the lighting in the office? And should we figure a dedicated 120-volt circuit for the 3 unit heaters?
 - o **Response** Electrical design/build is delegated to the Contractor. Electrical work shall be per the current adopted version of the applicable electrical code. Coordinate with Owner during Construction. See sheet G001- Building Envelope Requirements Table Semi-heated Space Note #2 for shop heater output limits.
- **Contractor Question** Building #2 A101: Is there a panel required? Is there a requirement for 120-volt outlets? Any other power outlets? Is there any unit heaters required?
 - o **Response** Electrical design/build is delegated to the Contractor. Electrical work shall be per the current adopted version of the applicable electrical code. Coordinate with Owner during Construction. This space is intended for equipment storage only and is not intended to be a conditioned space.
- **Contractor Question** Building #2 A103: Is there a requirement for emergency lighting inside the building?
 - o **Response** Emergency power for illumination requirements are per A103 Means of Egress Illumination Notes #3 & #4. The floor areas required to be illuminated by Emergency Egress Lighting are also shown on Sheet G001 Egress Plan.
- *Contractor Question* Building #2 A103: What is the spec on conduit? Is there a spec?
 - Response Electrical design/build is delegated to the Contractor. Electrical work shall be per the current adopted version of the applicable electrical code and/or EPUD standards, where applicable.
- *Contractor Question* Building #2 A103: Is there any information that we need to know about?
 - o **Response** The subject of this question is not clear.

End of Addendum #2



EXPIRES: 12/31/24

Branch Engineering, Inc. 3 of 3

SECTION 020 COBURG OPERATIONS BUILDING AND OPERATIONS STORAGE BUILDING PROJECT SCOPE OF WORK

Requirements of Project:

The project involves construction of a new operations building and separate storage building at the wastewater treatment plant at 91611 N Coburg Road, Coburg, Lane County, Oregon. The work involves: the construction of a new operations building and separate storage building, associated utilities, and asphalt and concrete paving. The Engineer's Estimate for this Project is approximately \$900,000-\$950,000.

Location of Project:

The project is located at the City of Coburg's wastewater treatment plant at 91611 N Coburg Road in Coburg, Lane County, Oregon.

Purpose of Project:

The purpose of the project is to provide the City of Coburg with the space and storage necessary for operations and maintenance of city owned utilities.

Project Engineer:

All questions should be directed to:

Julie Leland, P.E., Branch Engineering 541-746-0637 juliel@branchengineering.com

City Schedule:

Bids Closed / Opened & Read: 2:00 PM, July 20, 2023

310 5TH STREET, SPRINGFIELD, OR 97477

Projected Award Date:

Projected Start Date:

Substantial Completion Date:

Final Completion Date:

August 8, 2023

August 21, 2023

June 28, 2024

July 26, 2024

June 20, 2023





Coburg Operations Building City of Coburg Public Works 91136 N. Willamette St. Coburg, OR

RE: GEOTECHNICAL ENGINEERING INVESTIGATION

TAX MAP AND LOT NO. 16-03-28-00-0200

91611 N COBURG RD COBURG, OREGON 97408

BRANCH ENGINEERING INC. PROJECT NO. 20-004J

Pursuant to your authorization, Branch Engineering Inc. (BEI) performed a geotechnical engineering investigation at the subject site located at the above listed address. This report is intended fulfill the requirements in Section 1803 of the 2022 Oregon Structural Specialty Code (OSSC, 2022) and presents the results of our site research, field exploration and testing, data analyses, as well as our conclusions and recommended geotechnical design parameters for the project.

We appreciate the opportunity to be of service to you. Please contact the undersigned if you have questions or concerns regarding this report.

Sincerely, Branch Engineering Inc.



Perrick Digitally signed by Ronald J. Derrick Date: 2023.06.21 08:45:19 -07'00'

EXPIRES: 12/31/2023 Ronald J. Derrick, P.E., G.E. Principal Geotechnical Engineer

Andrew J. Park, E.I. **Engineering Designer**

TABLE OF CONTENTS

1.0	INTRODUCTION	
1.1	Purpose and Scope of Work]
1.2		1
1.3	Site information Resources]
2.0	GEOLOGIC SETTING	
2.1	Regional Geology	2
2.2	Site Geology	2
3.0	SITE SUBSURFACE CONDITIONS	2
3.1	Subsurface Soils	2
3.2	Groundwater	3
4.0	GEOLOGIC HAZARDS	3
5.0	CONCLUSIONS	4
6.0	DESIGN RECOMMENDATIONS	5
6.1	Foundation Subgrade Preparation Recommendations	5
6.2	Bearing Capacity	6
6.3	Settlement	6
6.4	Friction Coefficient and Lateral Earth Pressures	(
6.5	Site Parking, Slab-on-grade, and Accessway Subgrade Recommendations	(
6.6	Slabs-On-Grade	6
6.7	Pavement Design	6
6.8	Structural Fill	7
6.9	Seismic Design Parameters	7
7.0	CONSTRUCTION CONSIDERATIONS	8
7.1	Wet Weather/Dry Weather Construction Practices	8
7.2	Excavations	8
7.3	Slopes	8
7.4	Site Drainage	S
7.5	Expansive Soil Mitigation Strategies	S
7.6	Geotechnical Construction Site Observations	9
8 N	DEPORT LIMITATIONS	10

FIGURE 1 - Site Vicinity Map

FIGURE 2 – Exploration Map

FIGURE 3 - Geologic Mapping

APPENDIX A – Figure A-1 USCS Soils Key, Exploratory Test Pit Logs, OWRD Well Logs

APPENDIX B - Recommended Earthwork Specifications

1.0 INTRODUCTION

1.1 Purpose and Scope of Work

The purpose of this work is to establish and present geotechnical engineering criteria and requirements related to the site and subsurface conditions that may influence the design and construction of the proposed project. Our scope of work included a field reconnaissance with subsurface investigations performed by BEI personnel, and engineering data review of existing geologic and geotechnical reports, and other pertinent site research activities that culminated in the preparation of this report.

1.2 Project Location and Description

The project site consists of a parcel of land totaling approximately 50-acres in size located at the approximate coordinates of 44.1521° north latitude and 123.0625° west longitude north of Coburg, Oregon (see Figure-1 Vicinity Map) on a mostly rectangular tax lot. The site is bordered by undeveloped grass fields with Interstate 5 right-of-way abutting the site to the East.

The proposed build site is generally flat with the surface mainly consisting of clay and crushed rock and is currently occupied by a wastewater treatment facility, a commercial building, and two smaller structures on the southwest corner of the lot. Past aerial photography provided by Google Earth shows that the commercial building and treatment plant were constructed in 2012.

The project consists of two new steel framed structures that will be built in the area shown on the attached Figure-2, along with parking and associated utilities. Anticipated foundation loads are expected to be less than 2 kips per foot line loads and column loads less than 25 kips based on the structural design performed by BEI's in house structural engineer.

1.3 Site information Resources

The following site investigation activities were performed and literature resources were reviewed for pertinent site information:

- Two (2) test pit excavations were excavated on January 11, 2023 to a maximum depth of 36-inches below ground surface (BGS).
- One (1) Dynamic Cone Penetration test (DCP) to a depth of approximately 5-feet BGS
- Review of the Web Soil Survey of Lane County Area, United States Department of Agricultural (USDA) Natural Resources Conservation Service (NRCS) (attached in Appendix A).
- Review of Oregon Department of Water Resources Well Logs (attached in Appendix A).
- Oregon Department of Geology and Mineral Industries (DOGAMI) web hazard viewer.
- Review of the Geology of the Southern Willamette Valley Benton, Lane, Linn, Marion, and Polk Counties, Oregon 2010 DOGAMI Open-File Report O-10-03.
- Review of previous BEI investigations performed in the general area of the subject site.

- Geology of Oregon, sixth edition by Orr, Orr and Baldwin, 2012.
- Oregon Structural Specialty Code 2022 (OSSC 2022), applicable building code criteria

2.0 GEOLOGIC SETTING

The following sections describe the regional and local site geology:

2.1 Regional Geology

The subject site lies within the southern portion of the Willamette Valley, west of the Cascade Mountains Provinces and east of the Oregon Coast Range. In Oregon, the Willamette Valley is an elongate basin which narrows at both ends before terminating at the Calapooya Divide to the south and the Columbia River to the north. The basin is approximately 130 miles long and 40 miles wide. The valley is drained by the Willamette River and drops from an elevation of approximately 400-feet at Eugene, to near sea level at the northern end of the basin where the Willamette River drains into the Columbia River.

The Willamette River Valley in the area of the subject site is believed to be heavily influenced by historic hydrology, including the movement and sediment deposition of the McKenzie, Middle, and Coast Forks of the Willamette Rivers. The Willamette River once occupied the wetland areas of west Eugene and frequently overflowed onto the low-lying floodplains. During the last deglaciation and the resulting termination of the Last Glacial Maximum in North America, the Willamette Valley was cyclically flooded by catastrophic breaks in the ice dams of Glacial Lake Missoula. Occurring several times over an approximately 2,000-year period between 13,000 to 15,000 ago, these flood events filled the valley to an elevation of 350- to 400-feet before retreating, causing sequences of upward fining deposits of silt and clay that may or may not still be present in areas depending on erosion by subsequent fluvial actions. Much of these deposits have since become developed and urbanized.

2.2 Site Geology

The DOGAMI Geology of the Southern Willamette Valley Map show the geology of the site to be Quaternary age surficial deposits of alluvium, described as deposits of unconsolidated gravel, sand, silt, and clay deposited in active stream channels and on adjoining flood plains of major rivers and tributaries (see Figure-3, Geology Map). Site explorations were consistent with the mapped geology of the subject site.

3.0 SITE SUBSURFACE CONDITIONS

The analyses, conclusions and recommendations contained in this report are based on site conditions as they presently exist and assume that the results from our exploratory test pits presented in Appendix A are representative of the subsurface conditions throughout the site. If during construction, subsurface conditions differ from those encountered in the exploratory borings; BEI requests that we be informed to review the site conditions and adjust our recommendations, if necessary.

3.1 Subsurface Soils

Visual classification of the near surface soils was performed in accordance with the American Society of Testing and Materials (ASTM) Method D-2488 and the Unified Soil Classification System (USCS). The subsurface investigation utilized an excavator to advance 2-test pit excavations to a maximum depth of 36-inches BGS. In the test pits during our visit the observed soil profile consists of a mixture of silt and fine sand below previously placed fill material. The exploratory test pits are logged below.

- <u>Undocumented fill</u> was observed to be at the surface in all test pits and generally consisted of crushed rock and brown clayey gravels. The fill generally appeared to be loose and was damp to wet from rain on the day of our visit. Depth of fill ranged from 4- to 8-inches below current ground surface elevation.
- <u>Alluvial clay/silt</u> was observed to underlie the granular fill and was brown to dark brown and had medium plasticity. The dark brown soil may be the remnants of a topsoil section as trace organics were observed. This layer extended to depths of approximately 18- to -20 inches BGS.
- <u>Fine silty sand</u> was observed below the alluvial clays and appeared to be the location of the water table as evidenced by a moderate seep. The test pit exploration was terminated in this layer at 3-feet in both test pits.
- <u>Gravels</u> were likely encountered at approximately 5-feet BGS when refusal on a hard substrate was met during the Dynamic Cone Penetration test performed adjacent to TP-1.

We also reviewed nearby well logs obtained from the Oregon Department of Water Resources online database (attached in Appendix A) to determine soil conditions beneath the extent of our on-site explorations. The nearby well logs generally agree with our on-site explorations with fine-grained soils in the near surface to a depth of approximately 5-feet BGS and then gravel with sands that likely extend well over 50-feet below the site.

3.2 Groundwater

Groundwater seepage was first encountered in test pits TP-1 and TP-2 at approximately 24-inches when the fine sand soil was encountered. The excavation was left open for a short time to allow the groundwater level to stabilize which was approximately 12-inches BGS. We also performed a review of nearby well logs to determine the local and temporal variation in the regional water table. Groundwater was listed as being first encountered at 10-feet and 28-feet, which stabilized at depths of 2-feet and 5-feet. The higher elevation of the static water level may indicate a confined aquifer condition.

We expect that groundwater levels (from the regional water table or perched lenses) will fluctuate with the seasons and should be expected to be highest during the later winter and spring months when rainstorms are more intense and frequent, and soils are near saturation. The presence of groundwater is not expected to impact shallow foundations provided our recommendations are followed. Excavation will likely require dewatering, and should take place during the drier months of the year when groundwater levels are expected to be lower. Well logs from nearby sites obtained from the Oregon Department of Water Resources online database to the south and west of the subject site list static water levels of 2-feet to 5-feet BGS. The well logs are dated from January, and

May, when groundwater levels are typically at higher elevations during the year. During our visit, groundwater was first encountered at 24" below ground surface.

4.0 GEOLOGIC HAZARDS

OSSC 2022 (1803.5.11) required criteria for hazards the geotechnical investigation shall address for seismic class designations C through F are listed below.

- <u>Slope instability</u>: The site is not mapped as being at risk for land sliding. The potential for site landslides is low on the site due to the flat topography of the lot and surrounding terrain.
- <u>Liquefaction</u>: Liquefaction is caused by a rapid increase in porewater pressure within a saturated soil that reduces the interparticle friction between soil grains that can lead to the sudden loss of shear strength within the soil. This can cause a loss of bearing capacity, densification of subsurface soils that can lead to large surficial settlements, and the migration of soil particles to the surface in the form of sand boils. Loose, granular sands with a low fine-grained soil content and a recent depositional history are especially vulnerable to liquefaction. Saturation is required for a soil to experience liquefaction.

The DOGAMI online hazard viewer maps the site as moderate risk of liquefaction. The medium stiff sand in the area with groundwater encountered at 2-feet BGS poses a higher risk to liquefaction during a significant seismic event. The risk of liquefaction can be mitigated provided our recommendations are followed, however the high groundwater levels in the fine sands observed will still pose a moderate risk of liquefaction to the proposed development.

- Expected Earthquake Shaking: The site is mapped within a zone of very strong shaking that would typically be associated with the very large earthquakes generated from the Cascadia Subduction Zone off the Oregon coastline.
- Surface Displacement Due to Faulting or Seismically Induced Lateral Spreading or Lateral Flow: There no known faults on the site that could cause large surficial displacements. Surface displacement or seismically induced lateral spreading is not expected at the site.
- <u>Tsunami/seiche</u>: No major bodies of water capable of generating a Tsunami are near to the site. There is a small irrigation creek and pond to the east of the site, but this body of water is not large enough to be capable of generating a seiche or near enough to the build site to cause flooding. Therefore, the risk of a tsunami or seiche to affect the site is none.
- <u>Total and Differential Settlement</u>: See Section 6.3 below for a discussion of settlement risk.
- <u>Expansive Soils</u>: The silty sand soils have a low shrink/swell potential provided the subgrade soils beneath structural elements are prevented from undergoing fluctuations in moisture content.
- <u>Flood Risk</u>: The site is not mapped within the 100-year flood zone.

5.0 CONCLUSIONS

Based on our field observations, subsurface explorations, and data analyses, we conclude that the site is geologic and geotechnically suitable for the proposed development provided that the recommendations of this report are incorporated into the design and construction of the project. Our investigation did not reveal any specific site features or subsurface conditions that would impede the proposed design and construction of the project. The site has seasonal high groundwater levels. Excavation work should not be performed during the wet season, typically November through June.

6.0 DESIGN RECOMMENDATIONS

The following sections present site-specific recommendations for site preparation, drainage, foundations, utility excavations, and slab/pavement design. General material and construction specifications for the items discussed herein are provided in Appendix B. The following recommendations apply only to site work proposed in the southwest area of the site, adjacent to the existing structures, and any earthwork being performed in the central, north, and east end of the site may require alternative earthwork techniques.

6.1 Foundation Subgrade Preparation Recommendations

All areas intended to directly or laterally support structures shall be stripped of vegetation, organic soil, unsuitable fill, and/or other deleterious material such as moisture softened exposed soil in areas of new foundations. These stripping's shall be removed from the site or reserved for use in landscaping or non-structural areas. The depth to suitable subgrade for foundations is anticipated to be 1- to 2-feet BGS below any topsoil or undocumented fill layer and bearing on the medium stiff, brown sand.

Portions of the sandy soil underlying the topsoil zone were found to be soft, or loose. Following excavation to expose the sandy material we recommend using mechanical means to consolidate the material that will underlie foundations, prior to placement of the recommended engineered fill section described below. This may be accomplished by compacting the material with appropriate compaction equipment such as; a reversible diesel-powered plate compactor, smooth drum vibratory roller with a minimum gross weight of 10,000 pounds, or an excavator mounted hydraulic plate compactor (hoe-pack).

The compaction of the subgrade material in-place will only be possible with moisture contents found in the dry season, which is the recommended time for the building pad preparation due to seasonal ground water levels.

Once suitable native soils are reached, new foundations shall be underlain by an 18-inch-thick crushed aggregate section that extends a minimum of 18-inches horizontally beyond footing perimeters. The undocumented granular fill observed at the surface of the test pits may be reused for general fill outside of footing areas if properly moisture conditioned and compacted. All fills shall be prepared in accordance with Section 6.8 below.

Subgrade soils shall be observed by the geotechnical engineer of record (GER) and covered by compacted crushed aggregate in a timely manner to mitigate moisture fluctuations that may soften

or cause volume changes within the subgrade soil. If very soft subgrade soils are observed, improvement methods may be used such as removal and replacement with crushed aggregate fill that may be underlain by geotextile fabric or geogrid composites may be employed. If foundation areas are accessible, and if performed during the dry months of the year (June through October), subgrades may be proof rolled using a loaded, tandem-axle dump truck. Areas yielding excessively shall be scarified and re-compacted, or otherwise improved at the discretion and direction of the GER. A BEI representative shall approve exposed subgrade soils and observe any proof rolling activities.

6.2 Bearing Capacity

The structural design performed by BEI's in-house structural engineer used a presumptive bearing capacity of 1,500 psf for design. We take no expectation with the use of this value provided that the footing preparation recommendations listed in this report are utilized during construction of the building. The above bearing capacity may be increased by 1/3 for short term loading, such as wind or seismic events.

6.3 Settlement

The estimated total and differential settlement over a 20-ft span for new shallow foundations after project completion is not expected to exceed 1-inch and ½-inch between equivalently loaded footings, respectively.

6.4 Friction Coefficient and Lateral Earth Pressures

The proposed development does not currently include a need for determining lateral earth pressures. However, friction coefficient and lateral earth pressures can be provided if the development needs change.

6.5 Site Parking, Slab-on-grade, and Accessway Subgrade Recommendations

Based on our site explorations, the topsoil stripping depth in unimproved areas is approximately 8-to 14-inches BGS. Any undocumented fill encountered in roadway, parking areas, or slab subgrades shall be either removed to suitable subgrade soil or improved. In lieu of removal, undocumented fill may be improved to its full extent by scarification, moisture conditioning, and compaction using a roller with a minimum drum weight of 7,500 lbs or other suitable means of compaction. For fine grained soils, this would be most feasible during the dry months of the year, typically June through October. Prior to placing compacted crushed aggregate for the roadway structural section, the exposed subgrade shall be approved by the GER, or approved representative.

Proof rolls with a loaded 10 cubic yard haul truck, or equivalent vehicle, shall be conducted on the prepared aggregate section and any observed areas of deflection under load shall be corrected prior to placement of pavements. See Section 6.7 Pavement Design Recommendations for aggregate section and pavement thicknesses recommendations. Should grading plans require engineered fill, see Section 6.8 for engineered fill recommendations.

6.6 Slabs-On-Grade

New, interior, concrete slabs shall be underlain by a minimum of 18-inches of compacted, crushed aggregate once the subgrade is free of topsoil, soft soils, or unsuitable fill. A free draining aggregate

is recommended beneath structural slabs. The modulus of subgrade reaction (K) of the brown sandy soil at 1- to 3-feet below existing grade is 100 lb/in³ and the correlated California Bearing Ratio of the soil is correlated to be 3.

6.7 Pavement Design

We assume that areas of asphalt concrete (AC) planned for the site will be for site access or parking areas that will service lightly loaded vehicles. Should these assumptions prove incorrect or project conditions change, we request that we be informed so as to review and revise our recommendations, if needed

At the time of our investigation, grading plans for the proposed development were not available. The correlated California Bearing Ratio (CBR) for the silty sand is 3, which is a 'poor' classification. Following the removal of any unsuitable subgrade material, the subgrade soil is suitable for the placement of a pavement structural section consisting of Asphalt Concrete (AC) placed on compacted base rock. Our recommendations for any parking or driveway improvements used the guidance of the 1993 AASHTO Guide for Design of Pavement Structures and the 2003 revised Asphalt Pavement Design Guide, published by the Asphalt Pavement Association of Oregon, and calculated pavement structural sections based on similar soil profiles.

For the soils observed in the upper 3 feet of the site exploratory borings, a compacted aggregate base rock section consisting of a minimum of 10-inches of compacted aggregate on suitable subgrade is recommended. Additional excavation of soft, or loose material may be necessary to reach suitable subgrade. If removal of more material is needed to reach stiff sandy silt or rounded gravels the base rock thickness can be increased. For light vehicle traffic areas such as parking stalls a minimum of 3 inches of asphalt concrete (AC) pavement is recommended, 4-inches of AC is recommended to be used in accessways. Portland Cement Concrete (PCC) pavement shall consist of reinforced concrete slabs at least 6 inches in thickness.

Proof rolls with a loaded 10 cubic yard haul truck shall be observed on the compacted base rock prior to pavement installation and any areas of deflection under wheel loads shall be corrected by over-excavation and replacing subgrade material with additional compacted aggregate. The base rock shall be compacted to at least 95% relative compaction as determined by ASTM 1557/AASHTO T-180 (modified Proctor). The compaction of the base rock shall be tested prior to placement of asphalt concrete.

6.8 Structural Fill

All engineered fill placed on the site shall consist of homogenous material and shall meet the following recommendations.

- The recommended compaction level for crushed aggregate in structural areas and beneath pavements is 90 percent of the maximum dry density as determined by ASTM D-1557 (modified Proctor).
- Utility trenches located outside of the building area in pavement and load bearing areas should be backfilled with approved material and compacted to at least 90% of the maximum dry density.

- Prior to placement onsite, the aggregate or soil to be used shall be approved by the GER. If no recent Proctor curve (moisture-density relationship) is available for the material, a material sample will be required for testing to determine the maximum dry density and optimum moisture content of the aggregate or fill material. Use of the onsite soils for fill will require careful moisture conditioning and appropriate compaction equipment selection. Compaction of clayey soils during the wet season (November through June) will be difficult, if not impossible, to achieve due to insitu moisture contents being significantly higher than optimum moisture contents.
- Compaction shall be measured by on site testing with a nuclear densometer (ASTM D-6938), or sand cone method (ASTM D-1556) on structural fill with thicknesses in excess of 12-inches. If compaction testing is not feasible for any onsite or imported material due to factors such as oversize rock content or variable material, proof rolls with a fully loaded 10 cubic yard haul-truck or equivalent equipment shall be observed at regular intervals. Any observed areas of excessive yielding or rutting will require removal and replacement with granular fill or moisture conditioning and recompaction.
- Structural fill shall be moisture conditioned to within +/- 2% of optimum moisture content and compacted in lifts with loose thicknesses not exceeding

6.9 Seismic Design Parameters

Based on the soil properties encountered in our explorations and from nearby well logs, we recommend a Seismic Site Class D, stiff/dense soil (Table 20.3-1 ASCE 7-16) for the design of site structures.

7.0 CONSTRUCTION CONSIDERATIONS

7.1 Wet Weather/Dry Weather Construction Practices

The near surface fine-grained soils, if left exposed to prolonged precipitation, will become saturated and soften. Subgrade soil below foundations, slabs, and pavements shall be covered with compacted aggregate in a timely manner after excavation to minimize moisture fluctuations. BEI recommends that foundation subgrade preparation and general site earthwork be performed during the dry season—generally June through October.

Construction during the wet season may require special drainage considerations, such as covering of excavations, pumping to mitigate standing water in footing excavations, or over-excavation of moisture softened soils. Construction traffic should not be allowed to drive directly on exposed subgrades. Construction traffic routes will also be more susceptible to "pumping" and rutting during the wet season and will likely require thicker rock sections.

7.2 Excavations

Conventional Excavation equipment in proper working order should be capable of making the excavations necessary for foundations and other site improvements. The site soils are classified as OSHA Type C soils, due to loose sandy soil.

Branch Engineering, Inc.

We expect that the soils in the upper 3-feet will stand vertically, provided there is no groundwater seepage. Excavations below this depth will likely require sloping, benching, or shoring. Temporary construction slopes should not exceed 1:1 (H/V) and should be shallowed or shored if groundwater seepage is encountered. The crest of excavations or slopes should also be positioned at least 5-feet from any adjacent structure or improvement and heavy equipment or construction materials should not be stored within 10-feet of open excavations.

Caving and soil piping may occur in excavations that extend below the water table and dewatering will likely be necessary. The contractor is responsible for selecting an appropriate excavation method, shoring system, dewatering method, and should monitor excavations for safety. Excavations should be performed in accordance with the applicable safety guidelines outlined by OSHA and the state.

7.3 Slopes

Temporary slopes cut into native soil should not be graded steeper than 1:1 and permanent slopes (fill or cut) should not exceed a gradient of 2:1 unless specifically evaluated for stability.

7.4 Site Drainage

Alteration of existing grades for this project will likely change drainage patterns that should not adversely affect adjacent properties. Perimeter landscape and hardscape grades shall be sloped away from foundations and water shall not be allowed to pond adjacent to footings during or after construction.

7.5 Expansive Soil Mitigation Strategies

Surficial site soils are anticipated to be low to moderately expansive. We recommend the following precautions be adhered to during and after construction to help minimize the risk:

- Subgrade soils should not be allowed to dry out and should be covered with crushed rock in a timely manner to prevent moisture changes. Soils can be periodically wetted to maintain their insitu moisture content if excavation takes place during the drier months.
- Install roof gutters immediately after roof construction—unless during the dry season—and pipe them to a suitable disposal location.
- Sources of water should be prevented from saturating subgrades or becoming trapped below pavement surfaces and drainage structures should also not be located adjacent to pavement or other hardscapes.

7.6 Geotechnical Construction Site Observations

Periodic site observations by a geotechnical representative of BEI are recommended during the construction of the project; the specific phases of construction that should be observed are shown in the following table.

Table 1:

Recommended Construction Phases to be Observed by the Geotechnical Engineer						
At completion of subgrade excavation	Subgrade observation by the geotechnical engineer before aggregate and geogrid (if applicable) placement.					


Branch Engineering, Inc.

Imported fill material	Observation of material or information on material type and source.		
Placement or Compaction of fill material	Observation by geotechnical engineer or test results by qualified testing agency.		

8.0 REPORT LIMITATIONS

This report has presented BEI's site observations and research, subsurface explorations, geotechnical engineering analyses, and recommendations for the proposed site development. The conclusions in this report are based on the conditions described in this report and are intended for the exclusive use of the addressee and their designated representatives for use in design and construction of the development described herein. The analysis and recommendations may not be suitable for other structures or purposes.

Services performed by the geotechnical engineer for this project have been conducted with the level of care and skill exercised by other current geotechnical professionals in this area. No warranty is herein expressed or implied. The conclusions in this report are based on the site conditions as they currently exist and it is assumed that the limited site locations that were physically investigated generally represent the subsurface conditions at the site. This report represents our findings and should site development or site conditions change, or if a substantial amount of time goes by between our site investigation and site development, we reserve the right to review this report for its applicability and adjust our recommendations. If you have any questions regarding the contents of this report, please contact our office.






civil • transportation structural • geotechnical SURVEYING

310 5th Street Springfield, OR 97477 p: 541.746.0637

www.BranchEngineering.com



SITE MAP SCALE: 1" = 50'

<u>LEGEND</u>

INDICATES APPROXIMATE LOCATION OF EXPLORATORY TEST PIT

INDICATES APPROXIMATE LOCATION OF DCP TEST


EXPLORATION MAP

91611 N. COBURG ROAD, COBURG, OREGON

FIGURE-2

06-15-2023

PROJECT NO. 20-004j



SOURCE: DOGAMI OPEN FILE REPORT 0-10-03

SCALE: NOT TO SCALE

GEOLOGIC MAPPING

91611 N. COBURG ROAD, COBURG, OREGON

FIGURE-3

06-15-2023

PROJECT NO. 20-004j

APPENDIX A

USCS Exploration Key Test Pit Logs Wildcat Vane Shear Log OWRD Well Logs

RELATIVE DE	NSITY - COA	RSE GRAINED S	USCS GRAIN SIZE			
RELATIVE	SPT N-VALUE	D&M SAMPLER	D&M SAMPLER	FINES		< #200 (.075 mm)
DENSITY		(140 lbs hammer)	(300 lbs hammer)	SAND	Fine	#200 - #40 (.425 mm)
					Medium	#40 - #10 (2 mm)
VERY LOOSE	< 4	< 11	< 4		Coarse	#10 - #4 (4.75 mm)
LOOSE	4 - 10	11 - 26	4 - 10	GRAVEL	Fine	#4 - 0.75 inch
MEDIUM DENSE	10 - 30	26 - 74	10 - 30		Coarse	0.75 - 3 inch
DENSE	30 - 50	74 - 120	30 - 47	COBBLES	Codiso	3 - 12 inches
VFRY DENSE	> 50	> 120	> 47	CODDLLO		0 12 [[10103

CONSISTENCY - FINE GRAINED SOILS

CONSISTENCY	SPT N-VALUE	D&M SAMPLER	D&M SAMPLER	POCKET PEN. /	MANUAL PENETRATION TEST
		(140 lbs hammer)	(300 lbs hammer)	unconfined (TSF)	
VERY SOFT	< 2	< 3	< 2	< 0.25	Easy several inches by fist
SOFT	2 - 4	3 - 6	2 - 5	0.25 - 0.50	Easy several inches by thumb
MEDIUM STIFF	4 - 8	6 - 12	5 - 9	0.50 - 1.00	Moderate several inches by thumb
STIFF	8 - 15	12 - 25	9 - 19	1.00 - 2.00	Readily indented by thumb
VERY STIFF	15 - 30	25 - 65	19 - 31	2.00 - 4.00	Readily indented by thumbnail
HARD	> 30	> 65	> 31	> 4.00	Difficult by thumbnail

UNIFIED SOIL CLASSIFICATION CHART

MAJOR DIVISIO	NS		GRC	DUP SYMBOLS AND TYPICAL NAMES
COARSE-	GRAVELS: 50% or more	CLEAN GRAVELS	GW GP	Well-graded gravels and gravel-sand mixtures, little or no fines. Poorly-graded gravels and gravel-sand mixtures, little or no fines.
GRAINED SOILS:	retained on	GRAVELS WITH	GM	Silty gravels, gravel-sand-silt mixtures.
More than	the No. 4 sieve	FINES	GC	Clayey gravels, gravel-sand-clay mixtures.
50% retained	6 4 1 1 D G 5 C G G	CLEAN CANDS	SW	Well-graded sands and gravelly sands, little or no fines.
on No. 200 sieve	SANDS: 50% or more passing the No. 4 sieve	CLEAN SANDS	SP	Poorly-graded sands and gravelly sands, little or no fines.
		Sands with	SM	Silty sands, sand-silt mixtures.
		FINES	SC	Clayey sands, sand-clay mixtures.
FINE-GRAINED		HOUDINAT	ML	Inorganic silts, rock flour, clayey silts.
SOILS:		LIQUID LIMIT LESS THAN 50	CL	Inorganic clays of low to medium plasticity, lean clays.
Less than	CILT AND CLAY	LESS THAN SU	OL	Organic silt and organic silty clays of low plasticity.
50% retained	SILT AND CLAY	1101110 11111 50	MH	Inorganic silts, clayey silts.
on No. 200		LIQUID LIMIT 50 OR GREATER	CH	Inorganic clays of high plasticity, fat clays.
sieve		OR GREATER	ОН	Organic clays of medium to high plasticity.
Н	GHLY ORGANIC SO	DILS	PT	Peat, muck, and other highly organic soil.

MOISTURE CONTENT

DRY: Absence of moisture, dusty, dry to the touch DAMP: Some moisture but leaves no moisture on hand

MOIST: Leaves moisture on hand

WET: Visble free water, usually saturated

	PLASTICITY	DRY STRENGTH	DILATANCY	TOUGHNESS
ML	Non to Low	Non to Low	Slow to Rapid	Low, can't rol
CL	Low to Med.	Med. to High	None to Slow	Medium
MH	Med. to High	Low to Med.	None to Slow	Low to Med.
CH	Med. to High	High to V.High	None	High

STRUCTURE

STRATIFIED: Alternating layers of material or color > 6mm thick.

LAMINATED: Alternating layers < 6mm thick.

FISSURED: Breaks along definate fracture planes.

SLICKENSIDED: Striated, polished, or glossy fracture planes. BLOCKY: Cohesive soil that can be broken down into small

angular lumps which resist further breakdown.

LENSES: Has small pockets of different soils, note thickness. HOMOGENEOUS: Same color and appearance throughout.

LIST OF ABBREVIATION & EXPLANATIONS

SPT Standard Penetration Test split barrel sampler

D&M Dames and Moore sampler

Atterberg Liquid Limit

PL Atterberg Plastic Limit

Pocket Penetrometer

VS Vane Shear

G Grab sample

MC Moisture Content

MD Moisture Density

UC Unconfined Compressive Strength

DCP Dynamic Cone Penetrometer

TABLE A-1



Branch GEOTECHNICAL INVESTIGATION

EXPLORATORY KEY

15

14

15

WILDCAT DYNAMIC CONE LOG

Page 1 of 1

 PROJECT NUMBER:
 20-004J

 DATE STARTED:
 01-11-2023

 DATE COMPLETED:
 01-11-2023

HOLE #: DC-1

CREW: AP, Brian, Brooke SURFACE ELEVATION:

PROJECT: Coburg Ops building WATER ON COMPLETION:

ADDRESS: 91611 N Coburg Rd HAMMER WEIGHT: 35 lbs.

LOCATION: Coburg, Oregon CONE AREA: 10 sq. cm

	BLOWS	RESISTANCE	GRAPH OF CONE RESISTANCE		TESTED CO	NSISTENCY
DEPTH	I PER 10 cm	Kg/cm ²	0 50 100 150	N'	NON-COHESIVE	COHESIVE
-	24	106.6	•••••	25+	MEDIUM DENSE	VERY STIFF
_	10	44.4	•••••	12	MEDIUM DENSE	STIFF
- 1	ft 5	22.2	•••••	6	LOOSE	MEDIUM STIFF
_	5	22.2	•••••	6	LOOSE	MEDIUM STIFF
-	4	17.8	•••••	5	LOOSE	MEDIUM STIFF
- 2	ft 5	22.2	•••••	6	LOOSE	MEDIUM STIFF
_	8	35.5	•••••	10	LOOSE	STIFF
_	8	35.5	•••••	10	LOOSE	STIFF
- 3	ft 7	31.1	•••••	8	LOOSE	MEDIUM STIFF
- 1 m	4	17.8	••••	5	LOOSE	MEDIUM STIFF
_	4	15.4	••••	4	VERY LOOSE	SOFT
- 4	ft 4	15.4	••••	4	VERY LOOSE	SOFT
_	4	15.4	••••	4	VERY LOOSE	SOFT
_	4	15.4	••••	4	VERY LOOSE	SOFT
- 5	ft 15	57.9	•••••	16	MEDIUM DENSE	VERY STIFF
_	45	173.7	•••••	25+	DENSE	HARD
_						
- 6	ft					
_						
- 2 m						
- 7	ft					
_						
_						
- 8	ft					
_						
_						
_ 9	ft					
_						
_						
- 3 m 10	ft					
_						
_						
_						
- 11	ft					
_						
- 12	ft					
_						
- 4 m 13	ft					
I III 13						
		L	l .			

LANE 69599

STATE OF OREGON WATER SUPPLY WELL REPORT

(as required by ORS 537.765)

WELL	I.D.	#L	97367

START CARD # 199951

Instructions	s for com	pleting th	is report are or	the las	t page o	f this form.		START CA	KD #		
(1) LAND Name City			We	ell Numb	oer		(9) LOCATION (OF WELL (leg	al description	on)	
Address Po							Tax Lot 200		• Lot		
City Cobu	rg		State O	R	Zij	97408	Township 16	S	Range 3		W WM
(2) TYPE	of wo	RK	✓ New Well				Township 16 Section 28				
Deepenii 🗌	ng 🗌 Alt	teration (re	epair/recondition	n) 🔲 Ai	bandonn	nent 🔲 Conversion	Lat°	'" or		(de	egrees or decimal)
(2) DDII I	MEEL	IOD.					Long°	'" or		(de	egrees or decimal)
	Air 🗌 Ro	tary Mud	Cable A] Cable !	Mud	Street Address of W Eugene, OR 9740		lress) Near 9	1 <u>593 N. Col</u>	ourg Road
(4) PROP			/ 🔲 Industri	al 🗌	Irrigatio	on	(10) STATIC WA		rface.	Date 1-19-0 9	9
Thermal	□ II	njection	☐ Livesto	ck 🗌	Other _			ft. below land su	rface.	Date	
(5) DODE	HOLE	CONCT	DUCTION				Artesian pressure			Date	
Depth of Co	ompleted \	Well 140	ft.	•		ion: Yes No	(11) WATER BE Depth at which water	ARING ZONE	ES		
		_	,, <u> </u>				Depin at which water				
Diameter	RE HOL	E To	Material	From	SEAL	Sacks or Pounds	From	To	1	ted Flow Rat	1
	0	20	bentonite	0	20	32 sacks	10 34	138	75 gpm 100 gpn		2
6"	20	140	chips					130	100 gpii		
	<u> </u>										
							-				
How was se	al placed:	Metho	od 🗌 A	\square B	□ C	□D □E	(12) WELL LOG	·	ound Elevation	n	
			<u>10-340</u>				1 ` ′				
								erial	From 0	To	SWL
Gravel place	ed from _		ft. to ft	. Size	of grav	el	topsoil sand/gravels		5	60	2
(C) CACIN	JC / INI	e D				_	clay, tan		60	79	2
(6) CASIN		EK From	To Gauge	Stool	Placti	c Welded Threaded	sand/gravels		79	81	2
Casing: 6			40 .250	_	riasti		clay, w/sand/gra	vels	81	84	2
ошо <u>в</u> . <u>-</u>					\Box	y	clay, red		84	94	2
_							clay, tan red		94	105	2
							clay w/sand & gr	ravel	105	108	2
Liner:				_ 📙			clay, tan/red clay, tan w/sand	9 graval	108	130 134	2
_				_ ⊔	Ш		sand, cemented		134	138	2
Drive Shoe	used 🔲	Inside 🔲	Outside 🛮 No	ne			tuffs, dark grey	,	138	140	2
Final location	on of shoe	(s) 140'								110	
(7) PERF		ONS/SCI	REENS Method Sta	-			l				
_	orations				1/-						
☐ Scre	ens		Туре		Mai	erial	Date Started 1-12-	09	Completed _1	1-19 - 09	
From	To	Slot	Number Dia	meter		e Casing Liner	(unbonded) Water	Well Constructo	r Cartificatio	\n	
20	25	Size	75	l e	size						ening, alteration, or
32	25 60	1x3/8 1x3/8			'S 'S		abandonment of this	s well is in compli	iance with Ore	egon water su	pply well
	85	1x3/8			s	— %	construction standar		d and informa	tion reported	above are true to
	108	_	60		s		the best of my know	vledge and belief.			
129	134	1x3/8	100	P	s		WWC Number		Date		
(8) WELI		S: Minin	num testing ti ☐ Air			g Artesian					
	. –	_	_				(handed) \$57-4 \$50	All Constant	Contifferent		
Yield g	· .	Draw 13.40	aown D	rill stem		Time 3.5 hours	(bonded) Water W	ell Constructor (nenina altera	tion or
130 gpn		13.40	- 			J.J HOUIS	abandonment work				
well out	put	may flu	ctuate				above. All work pe	rformed during th	is time is in c	ompliance wit	th Oregon water
				A rtesie	Ela F	aund	supply well constru				
Temperatur						ound	and belief.				
			Yes By whon				WWC Number 63	6	Dieta	5_8_00	
Did any stra	ata contan	n water no	t suitable for in	TO	≅IVF	☐ Too little	M M Clanings - 630	101	Date_	5-8-09	
						-	Signed Cau	V Kne	ley si	レー	- AA AA
Depth of str	ıata:			MAV. 1	1 20	nq	Cheis	sten sen 1	NELL.	DRILL	us Co.

LANE 73004

STATE OF OREGON WATER SUPPLY WELL REPORT

(as required by ORS 537.765)

109684			
	109684	109684	109684

SI	ſΑ	RT	CA	RD	#	209363
----	----	----	----	----	---	--------

Instruction	s for com	pleting th	is report are o	n the las	t page o	f this form.		START CAR	J #		
(1) LAND Name Bet	OWNE	R lond	W	ell Numl	oer		(9) LOCATION (County Lane	OF WELL (legal	description	on)	
Address 9	1725 Win	nebago	Street				Tax Lot 2400		Lot		
City Eugene State OR Zip 97408					Township 16	S	Range 3		_W WM		
` ,			☑ New Well				Township 16 Section 29				
Deepen	ing 🔲 Ali	teration (r	epair/reconditio	n) 🔲 A	bandonn	nent Conversion	Lat° Long°	'" or	··········		degrees or decimal)
(3) DRIL	I. METH	OD					Long	or		(degrees or decimal)
Rotary .	Air 🔲 Ro	tary Mud	□ Cable □ A				Street Address of W Eugene, OR 9740	•	ss) <u>91725</u>	Winnebag	o St.
(4) PROPOSED USE Domestic Community Industrial Irrigation Thermal Injection Livestock Other							(10) STATIC WATER LEVEL 5 ft. below land surface. Date 5-16-13 ft. below land surface. Date				
							Artesian pressure				
				Special C	onstruct	ion: 🗌 Yes 💆 No	Artesian pressure	10. per squ	are men	Date	
Explosives	used:	Yes 🚺 N	ft. Type		Amour	nt	(11) WATER BE Depth at which wate				
	RE HOL				SEAL		From	To	Estimat	ted Flow Ra	ite SWL
Diameter 10"	From 0	To	Material bent. chips	From	To 19	Sacks or Pounds	28	55			
6"	19	19 60	bent, chips	U	19	13 sacks	55	60	100		5
	-	-									
									-		
How was s	eal placed:	Metho	d 🗆 A	Пв	ПС	ПD ПE					
Other _a					_		(12) WELL LOG	Grou	nd Elevation	n	
Backfill pla	aced from _		ft. to ft.	. Mat	erial			erial	From	To	SWL
Gravel place	ed from _		ft. to ft.	. Size	of grav	el	top soil		0	3	
							clay,sandy loam		3	5	
(6) CASI							gravels clay, brown		5 15	15 20	5
	iameter 1	From	To Gauge 9 .250	Steel		Welded Threaded	sand/gravels		20	30	5
Casing: 6		.5 5	9 .250	- 🖺	님		sand, brown/few	gravels	30	34	5
_				- H	Ħ	H H	sand, brown		34	35	5
_							sand/gravels, ce		35	37	5
Liner:							sand/few gravels		37	39	5
_				_ 🗆			sand/lops frave	HALLINA IV	39-31	60	5
Drive Shoe	used 🔲 I	nside 🗾	Outside No	ne							
Final locati	on of shoe	(s) 59					1 A A	AR 1 0 2014			
							- IVI	AR I V ZU			
(7) PERF)NS/SCF									
	forations		Method					SALEMA CYC			
☐ Scre	eens		Туре		mat	erial	Date Started 5-15-SALEM, OR Completed 5-16-13				
From	To	Slot Size	Number Diag	neter	Fele/pip size	e Casing Liner	(unbonded) Water I certify that the abandonment of this construction standar the best of my know	work I performed or well is in compliand ds. Materials used a	n the constr ce with Ore	uction, deep gon water su	
							WWC Number 188	16	Date		
(8) WELI		: Minin	num testing ti	me is 1	hour	g Artesian	Signed		Bate		
_	gal/min	Drawo		ــا rill stem	at	Time	(bonded) Water W				
100 55 60 1 hour					I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water						
well output may fluctuate					above. All work per supply well construct						
Temperature of water 50 Depth Artesian Flow Found and bel					and belief.	aon stantantis. This	s report is th	ac to the be	at of my knowledge		
			Yes By whom								
			t suitable for inte				WWC Number 97		Date		
Salty Muddy Odor Colored Other					Signed Mark M Mirestine						
Depth of st	rata:						Signed ///	FIII ()	ure	fur	

STATE OF OREGON		WEEE R.D. ERBEEN E 4	+119	
WATER SUPPLY WELL REPORT		START CARD#	69139	***
(as required by ORS 537.765 & OAR 690-205-0210)	1/6/2015	ORIGINAL LOG #		
(1) LAND OWNER Owner Well I.D.				
(1) LAND OWNER Owner Well I.D First Name Last Name	(9) LOC	ATION OF WELL (legal des	cription)	
Company BR FAMILY LTD PARTNERSHIP		NE Twp 16.00 S N/S		N E/W W/M
Address 90820 COBURG RD	Sec 28	1/4 of the W N E 1/4	1 Tay Lot 400	L/ VV VV IVI
City EUGENE State OR Zip 97408 (2) TYPE OF WORK New Well Deepening Conversion	Toy Mon Nu	mbos	I at	
(2) TYPE OF WORK New Well Deepening Conversion	1 Tax Map Nu	omber or		DMS or DD
Alteration (complete 2a & 10) Abandonment(complete	e 5a)			DMS of DD
(2a) PRE-ALTERATION	Long	Street address of well Neares	at address	- DIVIS OF DID
Dia + From To Gauge Stl Plstc Wld Thrd Casing:		OBURG RD	st address	
	91393 N CC	DBURG RD		
Material From To Amt sacks/lbs				
(3) DRILL METHOD	— (10) STA	TIC WATER LEVEL		
Rotary Air Rotary Mud X Cable Auger Cable Mud	(10) 51.11	Date	SWL(psi) +	SWL(ft)
Reverse Rotary Other		g Well / Pre-Alteration		
	Comple	ted Well 12/26/2008		10
(4) PROPOSED USE Domestic Irrigation Community		Flowing Artesian?	Dry Hole?	
Industrial/ Commercial Livestock Dewatering	WATER BEA	ARING ZONES Depth water	was first found 1	2.00
Thermal Injection Other	SWL Date		ow SWL(psi)	
			JW SWL(psi)	- SWL(II)
(5) BORE HOLE CONSTRUCTION Special Standard (Attach	0/20/2000			10
Depth of Completed Well 85.00 ft.	10/15/200	08 77 85 30		10
	sacks/			
	lbs			
10 0 20 Cement 0 20 20 S Calculated 5.37	S			
6 20 83 Calculated 5.37				
Calculated	(11) WEL	L LOG Ground Elevation	355.00	
How was seal placed: Method A B XC D E		Material	From	То
Other	top soil and		0	12
Backfill placed from ft. to ft. Material		and & Gravle	12	22
Filter pack from ft. to ft. Material Size	sand & grav		22	36
	sandy clay le		36	38
Explosives used: Yes Type Amount Amount	sand and gra	ale soft	38	75
(5a) ABANDONMENT USING UNHYDRATED BENTONITE	sand & clay	tight	75	80
Proposed Amount Actual Amount	sand and gra	ivle loose	80	85
(6) CASING/LINER				
(6) CASING/LINER Casing Liner Dia + From To Gauge Stl Plstc Wld	Thrd			
●		RECEIVED	BY OWE	
		TILOLIVLD	DI OVVIII	
				-
		FEB 0	2 2015	
			COL	
Shoe X Inside Outside Other Location of shoe(s) 84				
Temp casing Yes Dia From To		SALE	M. OR	
7) PERFORATIONS/SCREENS	_	0, (22)	101, 011	
Perforations Method				
Screens Type Material	Date Start	ed7/5/2008 Comple	eted 12/27/2008	
Perf/ Casing/ Screen Scm/slot Slot # of Te	ele/			
Screen Liner Dia From To width length slots pipe	Die) Water Well Constructor Certificat		
1		at the work I performed on the const		
		nt of this well is in compliance v		
		n standards. Materials used and inform	mation reported a	bove are true to
		my knowledge and belief.		
	License Nu	mber Date		
8) WELL TESTS: Minimum testing time is 1 hour	Signed			
Pump Bailer Air Flowing Artesian	n Signed —			
Yield gal/min Drawdown Drill stem/Pump depth Duration (hr)	(bonded) W	ater Well Constructor Certification	i e	
30 50 3	I accept res	ponsibility for the construction, deep	ening, alteration.	or abandonmer
		med on this well during the construction		
	performed of	during this time is in compliance	with Oregon wat	ter supply wel
Temperature 58 °F Lab analysis Yes By	construction	standards. This report is true to the b	est of my knowled	dge and belief.
	License Nur	mber 502 Date	1/6/2015	
Water quality concerns? Yes (describe below) TDS amount Description Amount Units	S			
	Contact Info	o (optional)		

LANE 73619

Page 1 of 1

		APPENDIX	Х В:
Recommende	ed Earthwo	ork Specifica	tions

GEOTECHNICAL SPECIFICATIONS

General Earthwork

- 1. All areas where structural fills, fill slopes, structures, or roadways are to be constructed shall be stripped of organic topsoil and cleared of surface and subsurface deleterious material, including but limited to vegetation, roots, or other organic material, undocumented fill, construction debris, soft or unsuitable soils as directed by the Geotechnical Engineer of Record. These materials shall be removed from the site or stockpiled in a designated location for reuse in landscape areas if suitable for that purpose. Existing utilities and structures that are not to be used as part of the project design or by neighboring facilities, shall be removed or properly abandoned, and the associated debris removed from the site.
- 2. Upon completion of site stripping and clearing, the exposed soil and/or rock shall be observed by the Geotechnical Engineer of Record or a designated representative to assess the subgrade condition for the intended overlying use. Pits, depressions, or holes created by the removal of root wads, utilities, structures, or deleterious material shall be properly cleared of loose material, benched and backfilled with fill material approved by the Geotechnical Engineer of Record compacted to the project specifications.
- 3. In structural fill areas, the subgrade soil shall be scarified to a depth of 4-inches, if soil fill is used, moisture conditioned to within 2% of the materials optimum moisture for compaction, and blended with the first lift of fill material. The fill placement and compaction equipment shall be appropriate for fill material type, required degree of blending, and uncompacted lift thickness. Assuming proper equipment selection, the total uncompacted thickness of the scarified subgrade and first fill lift shall not exceed 8-inches, subsequent lifts of uncompacted fill shall not exceed 8-inches unless otherwise approved by the Geotechnical Engineer of Record. The uncompacted lift thickness shall be assessed based on the type of compaction equipment used and the results of initial compaction testing. Fine-grain soil fill is generally most effectively compacted using a kneading style compactor, such as a sheeps-foot roller; granular materials are more effectively compacted using a smooth, vibratory roller or impact style compactor.
- 4. All structural soil fill shall be well blended, moisture conditioned to within 2% of the material's optimum moisture content for compaction and compacted to at least 90% of the material's maximum dry density as determined by ASTM Method D-1557, or an equivalent method. Soil fill shall not contain more than 10% rock material and no solid material over 3-inches in diameter unless approved by the Geotechnical Engineer of Record. Rocks shall be evenly distributed throughout each lift of fill that they are contained within and shall not be clumped together in such a way that voids can occur.
- 5. All structural granular fill shall be well blended, moisture conditioned at or up to 3% above of the material's optimum moisture content for compaction and compacted to at least 90% of the material's maximum dry density as determined by ASTM Method D-1557, or an equivalent method. 95% relative compaction may be required for pavement base rock or in upper lifts of the granular structural fill where a sufficient thickness of the fill section allows for higher compaction percentages to be achieved. The granular fill shall not contain solid particles over 2-inches in diameter unless special density testing methods or proof-rolling is approved by the Geotechnical Engineer of Record. Granular fill is generally considered to be a crushed aggregate with a fracture surface of at least 70% and a maximum size not exceeding 1.5-inches in diameter, well-graded with less than 10%, by weight, passing the No. 200 Sieve.
- 6. Structural fill shall be field tested for compliance with project specifications for every 2-feet in vertical rise or 500 cy placed, whichever is less. In-place field density testing shall be performed by a competent individual, trained in the testing and placement of soil and aggregate fill placement, using either ASTM Method D-1556/4959/4944 (Sand Cone), D-6938 (Nuclear Densometer), or D-2937/4959/4944 (Drive Cylinder). Should the fill materials not be suitable for testing by the above methods, then observation of placement, compaction and proof-rolling with a loaded 10 cy dump-truck, or equivalent ground pressure equipment, by a trained individual may be used to assess and document the compliance with structural fill specifications.

Utility Excavations

- 1. Utility excavations are to be excavated to the design depth for bedding and placement and shall not be over-excavated. Trench widths shall only be of sufficient width to allow placement and proper construction of the utility and backfill of the trench.
- 2. Backfilling of a utility trench will be dependent on its location, use, depth, and utility line material type. Trenches that are required to meet structural fill specifications, such as those under or near buildings, or within pavement areas, shall have granular material strategically compacted to at least the spring-line of the utility conduit to mitigate pipeline movement and deformation. The initial lift thickness of backfill overlying the pipeline will be dependent on the pipeline material, type of backfill, and the compaction equipment, so as not to cause deflection or deformation of the pipeline. Trench backfill shall conform to the General Earthwork specifications for placement, compaction, and testing of structural fill.

Geotextiles

1. All geotextiles shall be resistant to ultraviolet degradation, and to biological and chemical environments normally found in soils. Geotextiles shall be stored so that they are not in direct sunlight or exposed to chemical products. The use of a geotextile shall be specified and shall meet the following specification for each use.

Subgrade/Aggregate Separation

Woven or nonwoven fabric conforming to the following physical properties:

•	Minimum grab tensile strength	ASTM Method D-4632	180 lb
•	Minimum puncture strength (CBR)	ASTM Method D-6241	371 lb
•	Elongation	ASTM Method D-4632	15%
•	Maximum apparent opening size	ASTM Method D-4751	No. 40
•	Minimum permittivity	ASTM Method D-4491	$0.05 \mathrm{S}^{-1}$

Drainage Filtration

Woven fabric conforming to the following physical properties:

•	Minimum grab tensile strength	ASTM Method D-4632	110 lb
•	Minimum puncture strength (CBR)	ASTM Method D-6241	220 lb
•	Elongation	ASTM Method D-4632	50%
•	Maximum apparent opening size	ASTM Method D-4751	No. 40
•	Minimum permittivity	ASTM Method D-4491	0.5 S ⁻¹

Geogrid Base Reinforcement

Extruded biaxially or triaxially oriented polypropylene conforming to the following physical properties:

•	Peak tensile strength	ASTM Method D-6637	925
•	lb/ft Tensile strength at 2% strain	ASTM Method D-6637	200
	lb/ft	ASTM Method D-003/	300
•	Tensile strength at 5% strain	ASTM Method D-6637	600
	lb/ft	ACTIVATA ALL ALD 1000	
•	Flexural Rigidity	ASTM Method D-1388	250,000 mg-cm
•	Effective Opening Size	ASTM Method D-4751	1.5X
	rock size		